



CALGreen NOTES:

1. CHECK MOISTURE CONTENT OF BUILDING MATERIALS USED IN WALL AND FLOOR FRAMING BEFORE ENCLOSURE. (4.505.3)
2. PROTECT ANNULAR SPACES AROUND PIPES, ELECTRIC CABLES, CONDUITS AT EXTERIOR WALLS AGAINST THE PASSAGE OF RODENTS. (4.406.1)
3. COVER DUCT OPENINGS AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPENINGS DURING CONSTRUCTION. (4.504.1)
4. ADHESIVES, SEALANTS AND CAULKS SHALL BE COMPLIANT WITH VOC AND OTHER TOXIC COMPOUND LIMITS. (4.504.2.1)
5. PAINTS, STAINS AND OTHER COATINGS SHALL BE COMPLIANT WITH VOC LIMITS. (4.504.2.2)
6. AEROSOL PAINTS AND COATINGS SHALL BE COMPLIANT WITH PRODUCT WEIGHTED MIR LIMITS FOR ROC AND OTHER TOXIC COMPOUNDS. (4.504.2.3) VERIFICATION OF COMPLIANCE SHALL BE PROVIDED.
7. CARPET AND CARPET SYSTEMS SHALL BE COMPLIANT WITH VOC LIMITS. (4.504.3)
8. MINIMUM SORS OF FLOOR AREA RECEIVING RESILIENT FLOORING SHALL COMPLY WITH SECTION 4.504.4.
9. PARTICLE BOARD, MEDIUM DENSITY FIBERBOARD (MDF) AND HARDWOOD PLYWOOD USED IN INTERIOR FINISH SYSTEMS SHALL COMPLY WITH LOW FORMALDEHYDE EMISSION STANDARDS. (4.504.5)

SEE SHEET A1 FOR GENERAL NOTES.

DATE	REVISIONS

ENGINEER:  
**Paulo Ibanez P.E.**  
 7111 Aspen View Ct.  
 Citrus Heights, CA 95621  
 Ph. (916) 524-3052  
 Fax (916) 722-3579

DESIGNER:  
**d. i. potts drafting services**  
 Deanna Potts  
 7227 Main Ave.  
 Orangevale, Ca. 95662  
 Off./Fax (916) 988-7368

PROJECT: NEW CONSTRUCTION  
**PALM DRIVE**  
 COUNTY OF SACRAMENTO, CA. A.P.N. - 273-0400-003-0000  
 OWNER:  
**SCOTT & YVETTE GORDON**  
 6435 ORANGEHILL LANE CARMICHAEL, CA. 95608  
 PH. (916) 524-1833

**ARCHITECTURAL UPPER  
 FLOOR PLAN/NOTES**

DATE: 6-25-14  
 DRAWN: dlp  
 SCALE: 1/4" = 1'-0"  
 JOB# 14-723  
 SHEET:

**A2**

